Flooded Roads Put Infrastructure Crews on the Clock

Heavy rain in Florida and California shows how weather turns design, maintenance, and emergency jobs into public safety work.



A flooded urban road with a stalled car, barricades, and rainwater draining from a nearby building roof.

According to Associated Press reporting published by PBS NewsHour, a slow-moving storm system dumped heavy rain on South Florida, **flooding** roads, submerging cars, closing parts of the Florida Turnpike and Interstate 95, and causing the roof of Temple Sinai in Hollywood to collapse. No injuries were reported. Preliminary National Weather Service figures showed 15.3 inches of rain fell in parts of Broward County during a 24-hour period ending Wednesday. Hollywood declared a state of emergency, and officials in Broward and Miami-Dade counties announced that schools would be closed Thursday.

The weather was not just a local inconvenience. The National Weather Service warned that Florida's Atlantic Coast could see more rain through Friday, with an additional 12 inches possible. The Florida Division of Emergency Management warned of flash flooding, which is flooding that rises quickly enough to trap vehicles and people before they can react, along with dangerous surf and beach **erosion**. A low-pressure system, an area where rising air can help clouds and storms form, was also expected near the northern Bahamas and could develop into a subtropical or tropical storm near the Southeast and mid-Atlantic coasts.

A meteorologist with the National Weather Service in Miami said El Niño helped set up the pattern. El Niño is a natural warming cycle in the Pacific Ocean that can shift storm tracks and rainfall patterns far from where the ocean warming begins. In Florida, it disrupted the usual dry season and helped steer low-pressure systems toward the southeastern United States. That matters for planning because "normal" weather is what roads, drains, roofs, schedules, and staffing plans are often built around. When the pattern changes, crews find out fast where the weak points are.

The same broad stormy period affected the West Coast. In San Francisco, heavy rain and high winds grounded planes, canceled ferries, and flooded areas near the Ferry Building after waves came over flood **barricades**. San Francisco set a daily rainfall record with 2.28 inches. In Napa, Marin, San Mateo, and Santa Clara counties, highways were blocked by flooding or **debris**, according to transportation and highway patrol officials. A 47-mile stretch of Highway 1 near Big Sur was closed because of debris-flow risk, which means mud, rocks, water, and burned soil can rush downhill after rain.

For CTE pathways, the work behind this story is not abstract. A flooded road is part transportation

problem, part **drainage** problem, and part public safety problem. Public works crews, highway maintenance workers, equipment operators, utility workers, and traffic control technicians have to decide which lanes to close, where to place barricades, and how to keep stalled vehicles from becoming hazards. Stormwater technicians deal with the system that moves rain off streets, including inlets, pipes, ditches, pumps, canals, and **outfalls**, which are the discharge points where water leaves the system.

The roof collapse and hospital roof damage point to another set of trades. Building maintenance staff, roofers, inspectors, and **structural** engineers all deal with loads, meaning the forces a structure must carry. Rainwater adds weight fast when it ponds on a roof instead of draining away. On flat or low-slope roofs, drains, **scuppers**, **gutters**, and downspouts are not decoration; they are safety equipment. After a storm, the job may include checking for leaks, blocked drains, sagging roof sections, damaged ceiling systems, wet electrical areas, and mold risks.

Emergency management work connects all of these crews. Dispatchers handle calls for service. Police and fire departments respond to stranded drivers and flooded buildings. School districts decide whether buses and campuses can operate safely. Airport and ferry operators weigh wind, water, visibility, and equipment limits. Meteorologists supply forecasts, but local agencies still have to turn those forecasts into work orders, closures, staffing, and public warnings.

Getting hired into this kind of work depends on the role, but the useful skills are easy to see in the storm response. Employers need people who can read site conditions, follow safety procedures, communicate on radios, document damage, and work around moving traffic and energized equipment. Some jobs may require a commercial driver's license to operate large trucks, heavy-equipment experience, basic **surveying** or mapping skills, or knowledge of building codes. More technical roles, such as meteorology, civil engineering, and structural engineering, require more math, science, and formal education, but they still connect back to the same field conditions.

The storm also shows a trade-off that communities face before the water rises. Oversizing every drain, raising every roadway, hardening every shoreline, and upgrading every roof would be expensive and disruptive. Waiting until after repeated floods is also expensive, and sometimes dangerous. The work is to decide which risks are most likely, which failures would hurt people or shut down key services, and which fixes should come first. When the rain arrives, those earlier design and maintenance choices become visible on the street.

Written from reporting by PBS NewsHour.

THINK IT THROUGH

1. **If a city has limited money before the next major storm, should it prioritize road drainage, building inspections, emergency equipment, or public warning systems? Defend your choice.**

> **A strong answer:** A strong answer should weigh risk, cost, speed of improvement, and which option protects the most essential services.

2. **How should transportation agencies decide when to close a road that is flooded but still passable for some vehicles?**

> **A strong answer:** A strong answer should consider driver behavior, vehicle differences, emergency access, liability, and the danger of stalled cars.

3. **What skills from a trade or technical program would transfer best to storm response work, and what training would still be missing?**


> **A strong answer:** A strong answer should connect specific hands-on skills to field tasks while identifying gaps such as codes, incident command, forecasting, or traffic safety.

Flooded Roads Put Infrastructure Crews on the Clock

O A F K A I R E S R E R H E A U R R
S A E O R T E R T E R C O C R O L R
I I E R F D T E N L U R R N P C G V
B O N A R S M B T T E O N B R O R H
I I N S L L O S M C E S A O I T S E
U T D T D G L R L R D T R E E C C G
I N L T E R G U G J U U D F N O I T
A X E G R B A T Q L N I L S D T L L
O E A S U G A I R Y R T G Y E A R A
C U E I E T U R N Y F N S A B E I D
A S T R U C T U R A L L R E R L O R
I B P F T Y S E O I G S O L I E R I
S S T O A D A L R H C E R O S I O N
D S E G T L U S O S U A A G D R V T
U T D S D A L A N M O G D W G I L P
S C U P P E R S U S U R V E Y I N G
U R U G G U E E T A O L E U S T A G
D D G A O D E E S D R T O R A R D A

BARRICADES DEBRIS DRAINAGE EROSION FLOODING
GUTTERS OUTFALLS SCUPPERS STRUCTURAL SURVEYING

Flooded Roads Put Infrastructure Crews on the Clock



ACROSS

1 Points where collected water exits a pipe or canal

6 Temporary obstacles that close unsafe zones or reroute traffic

9 Water covering normally dry land, roads, or buildings

10 Roof-edge channels that collect and direct rainwater

DOWN

2 Concerning load-bearing parts that keep a building stable

3 Scattered storm leftovers, such as mud, rocks, and branches

4 Measuring and mapping a site for design or building work


5 Wearing away of soil or rock by water, wind, or waves

7 Network that carries rainwater away from surfaces

8 Roof-edge openings that let rainwater run off

Flooded Roads Put Infrastructure Crews on the Clock


— answer key



BARRICADES DEBRIS DRAINAGE EROSION FLOODING
GUTTERS OUTFALLS SCUPPERS STRUCTURAL SURVEYING

Flooded Roads Put Infrastructure Crews on the Clock

— answer key



ACROSS

1 Points where collected water exits a pipe or canal

6 Temporary obstacles that close unsafe zones or reroute traffic

9 Water covering normally dry land, roads, or buildings

10 Roof-edge channels that collect and direct rainwater

DOWN

2 Concerning load-bearing parts that keep a building stable

3 Scattered storm leftovers, such as mud, rocks, and branches

4 Measuring and mapping a site for design or building work

5 Wearing away of soil or rock by water, wind, or waves

7 Network that carries rainwater away from surfaces

8 Roof-edge openings that let rainwater run off

Where this came from

This article was written for 3andB from the reporting below. It is not a reprint — the wording is ours and the facts are theirs.

PBS NewsHour

"Rainfall supercharged by El Niño causes road flooding, synagogue roof collapse in South Florida"

Published	Wednesday, November 18, 2026
Read by us on	Thursday, November 19, 2026

https://www.pbs.org/newshour/nation/rainfall-supercharged-by-el-nino-causes-road-flooding-synagogue-roof-collapse-in-south-florida

WHAT IS IN THIS PACKET

The article with a note on each question, a word search, a crossword, and the answer key to both.

COPYING AND REUSE

Free to print, copy and hand out for classroom use. Please keep this page with the packet, so the next teacher can see where the story came from.

More where this came from

If this short lesson worked for your class, our full workbooks go further with the same care:

- Complete units with student and teacher editions
- Worked solutions for every exercise
- Standards-aligned, classroom-tested, print-ready

See the full lessons at 3andB.com

© 2026 3andB Inc.